U.S. ENERGY / MARKET ANALYSIS / PROJECT DELIVERY

U.S. Energy Projects From Plans to Delivery

An analysis of project development,
PMO and technical project leadership

Sven Zeh

November 13, 2026 | Professional analysis

Turning investment plans into
sound decisions and infrastructure ready to operate.

MARKET

Participants, incentives and regional constraints

DELIVERY

Accountability, approvals and technical interfaces

IMPACT

Reliable forecasts and measurable implementation

Focus: power supply, grids and generation projects.
With perspectives on adjacent energy sectors and the Carolinas.

www.svenzeh.com

01 / EXECUTIVE PERSPECTIVE

What makes energy projects deliver

The central management challenge is to turn many interdependent projects into dependable energy supply. Technical maturity, commercial viability and the ability to make decisions must progress together.

Large investment plans and extensive project pipelines demonstrate the scale of the challenge. They say less about when a plant will actually generate electricity or an industrial customer will receive its required connection capacity. Between demand and operation lie permits, grid studies, specifications, equipment deliveries, construction and approvals.

1. The market is fragmented by region and institution. The utility, network owner, regulator and system operator determine the development path. A national average cannot replace that project-specific assessment.

2. Some bottlenecks are integration problems. A technically sound work package can fail to deliver if its prerequisites sit in another contract, organization or permitting process.

3. Project leadership and PMO serve distinct purposes. The project leader integrates delivery. The PMO establishes dependable decision inputs, common working methods and visibility across projects.

4. Early clarity has economic value. Undefined scope, unconfirmed connection assumptions and late changes can commit capital before the execution basis is sound.

5. Impact needs evidence. Better reporting is not an end result. What matters is resolved interfaces, timely decisions, credible forecasts and demonstrated readiness to operate.

My conclusion

The strongest contribution of project management is to identify critical dependencies early and connect each one to an accountable owner, a sound decision and a result that can be verified.

Reading guide: Market and constraints: pp. 4-7. Delivery model and management disciplines: pp. 8-17. Technologies and regions: pp. 18-20. Application example, measures and implementation: pp. 21-23. References: pp. 24-27. Use the PDF bookmarks to navigate directly.

02 / PERSPECTIVE AND METHOD

Connecting technical work and leadership

My perspective on U.S. energy draws on three areas of work: technical project management in electrical infrastructure, the development of PMO structures in an industrial setting, and large power-generation project development. Together, they shape this report's questions: Is the project sufficiently defined? Are its interfaces under control? Can the responsible parties make decisions in time?

Professional background	Relevance to this analysis
Siemens: medium-voltage projects Technical and commercial delivery in an international environment.	The interaction of customer requirements, suppliers, equipment, schedule, quality and handover. The electrical interface is managed as a defined work package.
Schaeffler: PMO and development Establishing a PMO in the Hydrogen organization, including methods, steering forums and decision routes.	Repeatable project structures, coordinated milestones and a clear distinction between technical accountability and cross-functional coordination.
Uniper Kraftwerke: project development Coordinating engineering, permitting, procurement and commercial assessment during development.	Investment readiness depends on several connected forms of evidence. A development milestone does not establish that an asset has already been completed.

At Schaeffler, my PMO responsibility was a staff function. The focus was on methods and decision structures across disciplines. This experience is particularly relevant where specialists make sound decisions within their own areas but lack a shared workflow and a clear escalation route.

How to read this analysis

The market analysis uses publicly available primary sources: government agencies, regulators, system operators, research institutions, audit reports and company publications. It is structured secondary research, not my own survey of U.S. utilities. Figures carry a data year; plans and scenarios are identified as such.

The proposed roles, readiness criteria, measures and workflows are my professional interpretation of those sources and my experience. Their effectiveness must be assessed in the individual project using a documented baseline, consistent measurement rules and substantiated results.

Author perspective: personal professional experience. Market evidence: numbered sources. Proposed management methods: explicitly identified professional interpretation. No quantified performance improvement is claimed without supporting measurement.

03 / PARTICIPANTS AND ROLES

Who decides the outcome of an energy project?

U.S. energy has no single type of customer organization. For 2024, APPA counts, among other categories, 174 investor-owned utilities, 1,998 public utilities and 859 cooperatives. Its total of 3,371 utility entities includes several categories and U.S. territories. These are not 3,371 independent corporate groups. [1]

Participant and examples	Decision or responsibility	Critical interface
Regulated utilities Duke Energy, Southern Company, FPL	Demand, capital programs, assets and/or networks; regulatory cost recovery.	Project approval must align with resource planning, rate proceedings and capacity needs.
Network utilities Oncor	Connections and transmission/distribution expansion within their jurisdiction.	Studies, network upgrades, protection and outage windows determine whether an asset can be used.
Public power and cooperatives TVA, Santee Cooper, NCEMC	Regional supply, local distribution, or generation and wholesale procurement.	Local projects may depend on investments and commitments from upstream partners.
Competitive developers / generators NextEra Energy Resources, Vistra, Constellation	Siting, financing, offtake agreements, construction and operation of their assets.	Connection costs and market revenues influence investment approval and withdrawal.
Industry and data centers	Location, load profile, ramp-up and a dependable power supply date.	Credible load growth, contractual security and power delivery must align.
OEMs, EPCs and construction partners GE Vernova, Siemens Energy, Quanta, Burns & McDonnell	Equipment, engineering, procurement, construction and contracted performance.	Contract boundaries do not automatically match the functional boundaries of the complete asset.

Market structure and company roles are drawn from public company descriptions and reports. Constellation completed the Calpine acquisition in January 2026. Individual companies may perform several roles. [2], [3], [4], [5], [6], [7], [8], [9], [10]

Permitting authorities, local governments, landowners, affected communities, lenders and insurers also belong in the stakeholder assessment. Their requirements can influence siting, execution, financing and acceptance.

The project leader's first task: establish who orders, pays and approves, who sets technical requirements, and who is authorized to put the asset into operation.

04 / INCENTIVES AND CONTRACT BOUNDARIES

When legitimate project objectives conflict

FERC regulates interstate electric transmission and wholesale markets within its jurisdiction, among other responsibilities. State regulators decide important questions of regulated retail rates and utility investment. ISOs/RTOs coordinate regional system operations, markets and planning. That role does not make them the owner of every asset or the developer of every grid project. [11], [12]

Participant	Legitimate interest	Typical conflict
Utility / regulator	Reliable supply and reasonable customer costs.	Early network expansion creates capacity but can leave unused costs if expected load does not materialize.
Developer / capital provider	Predictable revenue, viable returns and bounded development exposure.	An attractive site can become uneconomic because of connection costs or a later grid date.
Industrial customer	Early production and dependable power.	The intended ramp-up may precede a firm utility commitment.
OEM / EPC / contractor	Defined scope, manageable liability and predictable utilization.	Open requirements become premiums, exclusions, change orders or schedule exposure.
Operations / maintenance	Safe, available and maintainable assets.	A short-term reduction in capital cost may shift effort and risk into operations.

Contracting execution does not remove owner responsibility

An EPC contract can integrate substantial scope. The owner still needs a complete view of owner-supplied items, permits, fuel, interconnection, operating readiness and contractual assumptions. Explicit exclusions deserve particular attention: a complete contractual package can remain functionally incomplete.

My approach is a joint interface review before award. Each handoff needs a deliverable, input requirement, acceptance criterion, date, document and accountable party. Gaps between contracted scope and operating requirements become explicit decisions.

Cost allocation belongs in development

Data centers illustrate this tension. Ohio addresses contractual commitments and financial security, among other provisions, to avoid shifting inappropriate large-connection costs to other customers. The applicable tariff must be assessed for the individual project. [13]

05 / MARKET AND CAPITAL

Investment scale is not delivery certainty

In 2025, U.S. utility-scale facilities generated approximately 4,429 TWh of electricity; small-scale solar added about 93 TWh. The rounded utility-scale mix was 41% natural gas, 24% renewables, 18% nuclear and 17% coal. This electricity view should not be equated with total energy consumption. [14], [15]

Where investor-owned utility capital is planned to go



Planned 2026 capital expenditures, $ billions; EEI, September 2026 plan data.

EEI reports $238.8 billion in planned 2026 capital expenditures. Transmission and distribution together account for $116.8 billion. The figures cover EEI's investor-owned electric utility group, not the entire U.S. energy industry. The gas-related category excludes gas-fired electric generation. [16]

Market signal	Project implication
Demand could grow substantially Berkeley Lab models a 649 TWh reference case for data-center electricity use in 2030, within a 521-843 TWh range.	Separate expansion phases, ramp-up assumptions and contractual load commitments. A national energy estimate cannot replace a local connection assessment.
Many projects seek interconnection Approximately 8,200 generation and storage projects were in the studied queues at year-end 2025.	Assess pipelines by maturity. A study application, connection agreement, financing and construction approval are different stages.

Data sources: [17], [18] Project implications are my professional interpretation.

Three different quantities

TWh measure energy over time. MW and GW measure power. Local network capacity determines whether that power can be transported at the required location. Project management must connect all three.

06 / DIAGNOSING CONSTRAINTS

What a PMO can influence

An effective response starts with the cause. A missing transformer, an unresolved system study and an unprocessed approval may produce the same schedule slip but require different interventions. The prioritization below is my qualitative assessment, not a statistical ranking of industry-wide causes.

Constraint	Underlying problem	Management contribution
1. Interconnection	Studies, network upgrades and project maturity progress on different timelines.	Complete inputs, control changes and integrate network and construction plans. Strong influence on own readiness; limited control over external capacity.
2. Transmission	Long planning, permitting and construction periods; multiple owners and regions.	Coordinate dependencies and approvals. Rights-of-way and physical expansion remain external requirements.
3. Uncertain load	Requests may diverge significantly from actual load growth.	Maintain scenarios, phases and decision thresholds; distinguish firm commitments.
4. Firm capacity	Generation, fuel and networks must work together during critical hours.	Include supply assumptions and technical evidence in approvals. This does not replace system planning.
5. Equipment	Manufacturing availability and specification maturity constrain procurement.	Identify early requirements, stabilize specifications and track releases and delivery evidence.
6. Specialist capacity	Several projects need the same scarce specialists.	Plan scarce roles across the portfolio and obtain explicit priority decisions.
7. Scope and change	Incomplete definition, late requirements and unclear contract boundaries.	A direct management opportunity: maintain traceable scope, cost basis, changes and accountability.
8. Resilience and cost	Extreme events and modernization needs meet affordability constraints.	Prioritize by risk and benefit, incorporating operations and customer impact.

Evidence includes large interconnection queues, long-range transmission programs, pressures from large-load requests, supply-chain constraints and resource adequacy risks. It does not establish a uniform shortage in every region. [18], [19], [20], [21], [22]

Diagnostic question: Is the obstacle technical, regulatory, commercial, organizational or a combination? Agree the action, accountable owner and deadline only after that diagnosis.

07 / THE DELIVERY MODEL

Project leadership, PMO and technical authority

A PMO becomes useful when its mandate addresses a specific management gap. Another reporting layer, without decision authority, data ownership or escalation, does little for delivery. I distinguish three functions: preparing portfolio decisions, coordinating a program and supporting individual projects with dependable controls.

Role	Core accountability	What must be explicit
Sponsor / steering committee	Objectives, funding, priorities and decisions beyond delegated authority.	Who can approve or change scope, budget and target dates? What triggers escalation?
Project leader	The integrated outcome within the mandate, including planning and active resolution of conflicts.	Which decisions can the role make? Which resources are firmly committed?
PMO / program management	Common methods, gate logic, portfolio visibility, data quality and decision follow-through.	Is the PMO advisory, assurance-focused or empowered with delegated delivery authority?
Project controls	Schedule model, cost forecast, progress, change and risk analysis.	Who provides inputs, validates forecasts and independently checks their credibility?
Engineering / operations	Technical design, discipline approvals, safety and operating requirements.	Technical approval authority and the criteria for testing and handover.
Procurement / commercial	Contract award, contractual position, changes and commercial assessment.	Binding orders and contract changes are made only by authorized parties.

Three routines provide a practical starting point

Weekly: resolve critical interfaces, upcoming approvals and blocked work. **Monthly:** update schedule and cost forecasts together with risks and changes. **Before each gate:** bring together demonstrated maturity, remaining uncertainty and the requested decision.

One decision, one accountable owner

Record the subject, authority, deadline, required evidence and outcome of each decision. The project leader remains accountable for execution; the PMO makes the decision process dependable and traceable.

08 / DECISION READINESS

Approvals require evidence of maturity

A calendar milestone is not, by itself, a sound authorization. What matters is whether the conditions justify the next commitment. The following model is my proposal for energy projects. Scope and evidence depth must fit the technology, contracting model and risk profile.

Decision	Minimum evidence	Reason to defer
G0: Development mandate	Need, intended outcome, sponsor, development budget and decision framework.	No clear customer or verifiable supply/business objective.
G1: Concept / site	Compared options; load or generation profile; land, grid and permitting assumptions.	A pivotal assumption is treated as confirmed without assessment.
G2: Investment / partial authorization	Defined scope, estimate basis, integrated schedule, contracts, risks and financing for the authorized scope.	Material exposure is neither quantified nor assigned to an accountable decision.
G3: Execution package	Executable documents, necessary permits, materials, site access and checked interfaces.	Work would start against unapproved design or inconsistent technical data.
G4: Commissioning	Test and switching documentation, safety approvals, utility coordination and an available operating organization.	Open safety- or function-critical items; a missing technical release.
G5: Acceptance / closeout	Demonstrated performance, contractual acceptance, handover documentation, and arrangements for punch-list items and warranties.	Operations cannot safely accept the asset, or material obligations remain unresolved.

Within its own scope, DOE requires disciplined front-end planning, accountable leadership, credible baselines and management of risk, change and performance. That logic is a useful reference. DOE Order 413.3C is not a universally binding standard for all U.S. utilities. [23]

Conditional approval is a deliberate risk decision

Each condition needs an owner, deadline, verifiable closure evidence and a limit on commitments permitted before closure. A green overall status must not hide unresolved conditions.

A limited early authorization may be appropriate for long-lead equipment. It should expose its own change, cancellation and commitment risks; it does not replace the later overall approval.

09 / INTERCONNECTION

Put the connection on the critical path

At year-end 2025, Berkeley Lab recorded approximately 1,312 GW of generation and 749 GW of storage in interconnection queues. For projects reaching operation in 2025 in the studied regions, the median interval from application to operation exceeded five years. These are generation and storage connections; the same waiting period cannot be assumed for an industrial load. [18]

FERC's generator interconnection reform strengthens cluster studies and project-readiness requirements, including site control and financial commitments. The applicable interconnection process, regional implementation and transition rules remain decisive. [24]

Workstream	Coordinating responsibility	Evidence that supports a decision
Technical inputs	Project leader with engineering, OEM and network partner.	Consistent data for power, operating mode, plant model and relevant protection/control requirements.
Assumptions and changes	Engineering owns technical content; the project leader assesses overall consequences.	A dated change register showing cause and effects on studies, equipment, costs and target dates.
Network-side work	Network partner delivers its work; project leader manages the interface.	Separate study, agreement, upgrade, testing and release milestones, with visible uncertainty.
Commercial commitments	Commercial, financing and authorized sponsor.	Payments, financial security, cost assumptions and exit provisions reflected in the investment model.
Commissioning	Commissioning lead, operations, protection specialists and network partner.	Agreed testing, communication and switching sequence with named approval authorities.

For large loads, the quality of the demand commitment also matters. Requested peak power, realistic ramp-up, expansion stages and contracted demand should be recorded separately. ERCOT identifies coordination requirements, backlogs and repeat studies in its large-load process. A request is therefore not secured future consumption. [20]

What project management can do

Improve the project's own inputs and decisions, expose the consequences of changes, and connect network work to the asset schedule. It cannot replace an external connection commitment or guarantee a queue position.

10 / SCOPE AND DEVELOPMENT MATURITY

What a cost case reveals about early planning

A specific audit is more informative than a general claim of poor project execution. The TVA Inspector General reviewed closure and restoration of the Gallatin Ash Pond Complex. Its initial estimate of about $899 million had risen to approximately $1.64 billion by July 2024, an increase of about 82%. The report was published in September 2025. [25]

The audit identified initially incomplete scope, an inadequately documented estimate basis, and weaknesses in reporting or approving changes. It establishes issues in that project. It is not evidence of an average cost overrun across the industry. [25]

My implications for project development

Failure mechanism	Action before authorization	Reviewable work product
Scope is described only as an equipment list. Supporting work and handoffs are missing.	Translate functional requirements into complete work packages, including owner inputs, demolition, testing and operating readiness.	Defined scope with exclusions, assumptions and accountable owners.
Costs appear more precise than the design.	Disclose estimate status and technical maturity; document quantities, pricing basis and uncertainty.	Estimate basis with date, data source and a risk-informed range.
Changes are assessed individually. Their combined effect is invisible.	Evaluate technical, schedule and commercial consequences together; escalate cumulative exposure.	Change summary with approved baseline, open decisions and total forecast.

GAO's cost guide connects the technical baseline to work breakdown structure, assumptions, data, risk assessment and updates using actual costs. This relationship matters: a correctly calculated estimate based on incomplete scope remains a poor decision input. [26]

Front-end planning must serve the next decision

Sufficient definition means understanding the next commitment: what is being ordered, what remains open, which change would be expensive and who accepts the residual uncertainty. More documents without that clarity add little value.

11 / INTEGRATED SCHEDULE MANAGEMENT

Dependencies determine the delivery date

A credible schedule models execution logic. It explains which conditions enable the next step and which delay affects the overall date. GAO's scheduling guide emphasizes integration and the relationship between schedule risk and cost. I apply that logic to the technical and external interfaces of an energy project. [27]

Three paths must converge before commissioning



Illustration only, not an actual project schedule. Add project-specific dependencies such as fuel, water, telecommunications and offtake agreements.

Management question	Implication for the schedule
What prevents the next step?	Link predecessors and approvals. An equipment delivery date without its preceding drawing release is incomplete logic.
How firm is an external date?	Distinguish contracted, coordinated, estimated and unresolved dates; record the source and update date.
How much float actually exists?	Derive float from the schedule logic. Several workstreams cannot independently consume the same buffer.
What would acceleration achieve?	Assess actions that affect the governing path, disclosing added costs and new risks.

Progress, forecast and authorization are different information. A package may be 90% complete and still block a critical approval. Alongside quantity-based progress, I would therefore report the remaining prerequisites for the next decisive milestone.

The central schedule-review question: Which prerequisite threatens the target, who can influence it, and what decision is needed by when? A status color alone does not answer those questions.

12 / PROCUREMENT AND SUPPLY CHAINS

Balance early ordering against early commitment

DOE documented typical transformer lead times increasing from three to six months in 2019 to twelve to thirty months in 2023. That historical range is not a current 2026 delivery commitment. In the third quarter of 2026, GE Vernova reported a global Gas Power equipment backlog and slot reservations totaling 122 GW. This is neither U.S.-only nor entirely firm equipment orders. [21], [28]

Project leaders face a trade-off. Ordering early may secure a manufacturing slot but commit the project to an unstable specification. Waiting may reduce change exposure while worsening the available delivery date. Management should see and decide that trade-off explicitly.

Clarify before an early commitment	Required decision
Technical maturity Which performance, grid, environmental and space requirements are confirmed?	Which open parameters materially affect manufacturing, price or approval? Which may legitimately be finalized later?
Delivery date Is the date indicative, reserved or contractually committed?	Which conditions, advance payments and releases preserve it?
Change and cancellation exposure What if the site, connection or concept changes?	What maximum committed amount and additional cost are acceptable, and who authorizes them?
Documents and testing What do construction, protection and operations need?	Agree document deliveries, test attendance and technical issue closure as specific milestones.
Logistics and installation Route, foundation, lifting, storage and site access.	Manufacturer readiness to ship and site readiness to receive must align.

Reduce variation where the function allows it

Standard specifications can simplify repeated review and procurement. The limit is the technical capability actually required. A procurement standard cannot override a different network requirement. The PMO can make exceptions visible; engineering and operations retain technical authority.

The management work product

A critical-procurement register connects the need date, technical release, purchase decision, documents, manufacturing, testing, transport and installation. A list of purchase-order numbers alone is insufficient.

13 / COST AND CHANGE

The forecast must match the technical position

A cost forecast is useful only when it reflects the same scope and schedule as the project. Financial accounting, commitments and expected remaining costs answer different questions. I would connect them through a common project structure while keeping their meanings distinct.

The logic of the estimate at completion

Expected final cost = actual costs to date + expected remaining costs.
Remaining costs include outstanding commitments and work not yet awarded. Costs already incurred must not be counted again within open purchase orders.

Component	Control requirement
Approved baseline	Document scope, schedule, cost and pricing basis. Change the baseline only through authorized decisions.
Estimate to complete	Assess remaining quantities, scope, hours, price movements and foreseeable rework; reconcile them with schedule and physical progress.
Change / claim	Track distinct states: identified, assessed, submitted, negotiated, approved or rejected. Show potential commercial exposure.
Risk and contingency	Define their treatment explicitly. Do not include the same uncertainty in package prices, remaining costs and another contingency allowance.
Forecast decision	Explain the variance: quantity, productivity, price, schedule, scope or risk. The project leader validates the integrated position.

GAO describes traceable, comprehensive estimates, updated with actual data, as a basis for dependable management. For me, each material forecast change needs an explanation and a connection to a work package, date or specific uncertainty. [26]

Use earned value where the prerequisites exist

Earned Value Management requires defined scope, a credible budget and clear progress rules. It can support repeatable construction packages. In early, rapidly changing development, an apparently precise earned-value number may instead create false confidence. Spending is not a substitute for demonstrated progress.

Decision discipline: An open claim is not automatically an accepted cost. It must still remain visible in the risk assessment. Contractual status and expected exposure are separate but reconciled information.

14 / PORTFOLIO AND RESOURCES

More projects require more than headcount

Projects share scarce roles: protection engineering, grid studies, commissioning, construction management, permitting and experienced project leadership. DOE's USEER-based account reports hiring difficulties among 76% of surveyed construction firms in electric power generation for 2025. That figure applies to this group, not all U.S. energy companies. [29]

My PMO experience supports looking beyond aggregate staffing. The question is which qualification must be available, and when, to enable an approval, test or commissioning activity. Additional general capacity does not necessarily resolve a specialist constraint.

Portfolio decision	Information needed	Possible action
Which projects are executable?	Scope, grid, permitting, financing and procurement maturity.	Prioritize by the next achievable decision; do not favor immature projects solely because they are large.
Which role limits throughput?	Demand by critical role, firm assignments, utilization and substitution options.	Resequence work, procure targeted support or standardize packages.
Where do commitments conflict?	The same people, suppliers, outage windows or operating assets appear in several plans.	Obtain one shared priority decision instead of accepting contradictory project commitments.
Which method can be reused?	Similar technical packages, approvals and recurring failure mechanisms.	Transfer tested templates and reviews while retaining local requirements and exceptions.

Standardization needs technical feedback

Industrial development offers useful maturity reviews, structured handoffs and a connection between quality and schedule. Energy projects still need their own logic. A product-development or APQP checklist should not be copied uncritically into a power plant, interconnection or permitting process.

Prioritization is a leadership decision

A scorecard can make options comparable. It must not mathematically offset a missing safety, permitting or connection prerequisite with favorable scores elsewhere. Mandatory criteria remain mandatory.

15 / DATA, TOOLS AND AI

Reliable data requires clear ownership

A digital PMO starts with common definitions and accountability. If scope, schedule, costs and changes use different project identifiers, additional software will not make reports dependable. The first task is to establish an authoritative relationship between the information.

Information object	Required content	Ownership
Project / work package	Unique identifier, scope, deliverable and accountable role.	Project leader and discipline owners.
Milestone / approval	Criterion, date, dependency, evidence and approval authority.	Project leader; technical approval by the authorized party.
Interface / open item	Required input, provider, recipient, due date and consequence.	Named owner on both sides.
Change / risk	Cause, affected packages, schedule/cost effect, status and decision.	Project leader with engineering, controls and commercial.
Cost / progress	Status date, source, accounting/forecast logic and validation.	Finance and controls; physical progress validated by the delivery owner.

Where AI can support the work

Useful applications include structuring meeting notes, flagging possible inconsistencies between document versions, and drafting a decision paper with source references. These remain support functions. Technical design, contract interpretation, approvals and binding status changes require the responsible professional review.

For a pilot, I would select a bounded workflow such as tracking open interfaces. Inputs, permissible data, document versions and reviewers are defined. The output is checked against the original source before entering the authoritative project record.

How to judge a tool

Can another person trace a status back to its source? Does it improve the speed and quality of decision preparation? Does it reduce unresolved duplication? An attractive dashboard without dependable data provenance does not meet those tests.

Proposed implementation approach: validate usefulness and data quality in the pilot. Access, privacy and confidentiality follow the individual company's requirements.

16 / LEADERSHIP THROUGH HANDOVER

Built does not mean ready to operate

The final phases bring distributed dependencies together. The asset, grid, protection, controls, utilities, personnel and documentation must all be ready at the same time. Commissioning therefore belongs in early project planning. Handover is more than a document folder assembled at the end.

State	What it actually means	Evidence required
Installation complete	The planned installation is in place. This does not establish completed functional testing.	Installation checks, inspection records and categorized punch-list items.
Ready for testing	The prerequisites for a specific test are satisfied.	Agreed test boundaries, test plan, required approvals and available participants.
Ready to energize / operate	The responsible parties authorize a defined operating state.	Technical/operational approvals, switching documents, utility coordination and safety evidence.
Performance demonstrated	Agreed functional and performance requirements have been tested.	Results with measurement conditions, acceptance criteria and assessed deviations.
Contractually accepted / commercially operating	The respective contractual conditions have been met. These terms are not automatically equivalent.	Acceptance decision, fulfilled contractual prerequisites and agreed residual obligations.

The project leader's practical responsibility

I would establish a joint readiness review with operations, commissioning, engineering, suppliers and the network partner. Each open item is categorized by consequence: does it prevent safe energization, restrict performance or concern follow-up documentation? Technical judgment determines the category, not a desire to report a green target date.

Handover also includes as-built records, maintenance instructions, spares, training, warranties and a controlled punch-list process. Operations must know which limitations have been accepted and who will remove them by when.

The boundary of PMO authority

The PMO organizes evidence and visibility. It does not thereby authorize switching, safety clearance or operation. Those decisions remain with qualified and authorized personnel.

17 / DIFFERENT ENERGY SEGMENTS

Each technology has its own delivery logic

A common PMO framework is useful, but decisive readiness and approval criteria differ across grids, generation and emerging energy carriers. The following view connects documented market activities with my interpretation of the management priorities.

Segment / examples	Where delivery is demanding	Project leadership priority
Grids and substations Oncor, Duke; Quanta, Burns & McDonnell	Connection dependencies, system studies, equipment, rights-of-way and work on existing networks.	Connect interfaces, technical data and outage windows early; standardize recurring packages.
Gas-fired generation Duke, Vistra; GE Vernova, Siemens Energy	Turbines, grid, fuel supply and permits must align in time.	Treat equipment and gas availability as distinct prerequisites; plan commissioning early.
Nuclear power Constellation; new reactor concepts	Stringent requirements for licensing, quality, configuration and evidence.	Disciplined change/document control; distinguish licensing stages from operational readiness.
Solar, wind and storage NextEra Energy Resources, utilities and developers	Connection, curtailment, operating profile and revenue model determine asset value.	Validate power, energy capacity, grid use and operating strategy together.
Gas transportation and LNG Kinder Morgan, Cheniere	Pipelines, compression, liquefaction, electricity supply and offtake form a chain.	Align capacity and commissioning assumptions across multiple operators.
Oil and refining ExxonMobil, Valero	Operating assets, limited shutdown windows and process integration.	Define changes and work on operating facilities carefully; prepare restart.
Hydrogen Industry, developers and technology suppliers	Production, power supply, transportation and firm offtake must form a viable business.	Assess technical maturity and the business model separately; link commitments to evidenced offtake and infrastructure.

Sources for activities and technical/commercial relationships: [4], [9], [10], [28], [30], [8], [3], [31], [32], [33], [34], [35], [36]. Management priorities are my interpretation.

Long Mott provides a current example of distinct project stages. In November 2026, the NRC announced a construction permit for the planned reactors. A construction permit is not an operating license. Portfolio reporting should preserve that distinction. [37]

18 / REGIONAL PRIORITIES

Regional risks require regional decisions

NERC's 2025 long-term assessment identifies resource adequacy challenges within ten years in 13 of 23 assessed North American regions. This is neither a U.S.-only finding nor a prediction of widespread blackouts. The regional cause is what matters for project assessment. [22]

Region / system	Documented signal	Resulting project priority
PJM / Mid-Atlantic	Capacity procurement for 2027/28 shows pressure on firm supply.	Focus on connection maturity, credible operating dates and supportable capacity assumptions.
MISO / Midwest	LRTP Tranche 2.1 comprises 24 projects totaling approximately $21.8 billion, targeting service in 2032-2034.	Manage multi-year programs across owners, permits and interdependent network projects.
Texas / ERCOT	Large-load connections require coordination and studies; requests are not realized demand.	Integrate load ramp-up, firm capacity, network upgrades and staged commitments.
California / CAISO	High solar output and periods of curtailment coexist with flexibility needs in other hours.	Assess operating profile, storage, network and commercial benefit together.
Carolinas / Southeast	Utilities plan or procure generation and storage; manufacturers expand capacity.	Integrate development, interconnection, suppliers and regional construction resources.
New England / ISO-NE	Gas dependence and winter conditions matter; ISO-NE also expects adequate energy and capacity for winter 2026/27.	Assess seasonal supply and fuel assumptions without assuming an immediate shortage.
Gulf Coast / LNG	EIA's November 2026 outlook forecasts U.S. LNG exports rising from 17.6 Bcf/day in 2026 to 19.0 Bcf/day in 2027.	Coordinate gas/power infrastructure, industrial expansion and offtake schedules.

Regional evidence: [38], [19], [20], [31], [2], [39], [30], [40], [41], [42]. Priorities are my interpretation. Bcf/day means billion cubic feet of gas per day.

Implication for project development

An initial site assessment should identify responsible parties, available connection options, relevant seasonal risks and the actual maturity of adjacent infrastructure. A low land price alone is not a dependable site advantage.

19 / FOCUS ON THE CAROLINAS

A connected market for project delivery

The Carolinas bring together utility projects, industrial demand, equipment manufacturers and local networks. That combination is more informative than a list of major company names. One investment can create interdependent tasks for the owner, manufacturer, network partner and contractor.

Documented development	Correct interpretation	Relevant delivery questions
Duke Energy / South Carolina August 17, 2026 resource-plan announcement, including 1,400 MW in Anderson County.	Approved or planned capacity is not yet an operating asset.	Which partial authorizations, grid/fuel assumptions and supply packages govern the next binding decision?
Duke / battery storage 2026 procurement program targeting approximately 400 MW of stand-alone, four-hour batteries.	Procurement target and program documents; this does not establish that participation is currently open.	How are connection, site, operating profile, equipment and acceptance criteria coordinated across packages?
Siemens Energy / North Carolina A $1 billion U.S. investment announcement, including Charlotte and Raleigh.	Company plan covering several locations and business areas.	How do capacity expansion, supply capability and customer delivery interact? Which interfaces arise?
GE Vernova / Greenville Planned $160 million manufacturing investment; an existing service and repair location.	Manufacturing expansion and service represent different project settings.	How can customer requirements, manufacturing releases, testing and site dates remain consistent?
Cooperatives / public power 26 local cooperatives in NC; NCEMC serves 25 members. Santee Cooper is another regional participant.	Local distribution and upstream power supply have separate responsibilities.	Which projects share people, suppliers or upstream network dependencies? Where would common program coordination help?

Project and company sources: [2], [39], [30], [43], [44], [5], [6]. Published projects do not establish a confirmed consulting or hiring need at an individual company.

My assessment: electrical interfaces, development readiness and coordination across investment packages are particularly relevant entry points. They connect medium-voltage experience, PMO implementation and power-project development. Any specific engagement still needs to be assessed against project status, mandate and the existing organization.

20 / ILLUSTRATIVE APPLICATION

When one open interface blocks the start

Scenario: an industrial company expands a site and needs a new supply connection with substation and medium-voltage equipment. This is a constructed example, not a customer engagement or a measured project result.

The equipment supplier reports manufacturing on schedule. Civil work is progressing. Production retains its ramp-up date. Yet the protection-coordination inputs are not finally confirmed. Planned commissioning requires an approved protection configuration and an agreed switching window.

Observation	Cause / consequence	Specific management response
Each workstream report appears credible.	Each party reports its own scope, but the combined readiness to operate is not fully evidenced.	Create one integrated list of prerequisites for energization and ramp-up.
A technical input stays unresolved.	Engineering, OEM and network partner use different assumptions or document revisions.	Define the authoritative data set, provider, reviewer and due date; resolve the technical discrepancy.
The consequence is recognized late.	Protection approval, testing and utility date are not fully linked in the schedule.	Add the dependencies and determine the impact on test and ramp-up dates.
Acceleration is requested indiscriminately.	More site hours do not remove a missing technical approval.	Compare effective options only: technical resolution, an adjusted test window or an acceptable staged ramp-up.

Distinct contributions from leadership and PMO

The project leader brings the parties together, evaluates options and obtains the decision. **The PMO** keeps the interface visible in the common schedule, risk and decision position. **Technical owners** validate the solution; the network partner and authorized operating personnel issue the required releases.

The verifiable result

An agreed data set, a closed technical interface, an updated schedule and a traceable approval. Only comparison with the baseline establishes whether waiting time, rework or schedule uncertainty actually decreased.

Electrical coordination resembles the work of medium-voltage project management. Repeatable tracking across projects is a PMO responsibility. Their combined application creates the potential benefit.

21 / MEASURING IMPACT

Measures that improve decisions

A PMO needs a documented baseline. The following indicators are proposals; targets are agreed after initial measurement. Consistent definitions and comparison rules determine whether the results are meaningful.

Indicator	Definition / data basis	Use and ownership
Decision cycle time	Median calendar days from a complete decision package to the decision; also show the oldest open cases.	Weekly; PMO and decision owner. Track incomplete submissions separately.
Overdue critical interfaces	Open overdue critical interfaces divided by all critical interfaces due by the cutoff; also show counts.	Weekly; project leader and interface owners. Control changes to due dates.
First-pass approval	Initial submissions approved without material rework divided by all initial submissions in the period. Critical conditions do not count as a pass.	At each review; PMO. An indicator of preparation quality.
Milestone forecast error	Absolute difference in days between the actual date and the forecast four weeks before the due date planned at that time.	Monthly; controls. Use a consistent horizon and identify scope changes.
Age of open changes	Calendar days since logging each open change, supplemented by schedule effect and commercial exposure.	Weekly; project leader and commercial. Prioritize by age and consequence.
Cost-forecast maturity	Share of material remaining-cost packages with current quantity/scope assumptions and a validated price basis. Define materiality in advance.	Monthly; controls and package owners. Close gaps in supporting evidence.
Handover readiness	Completed mandatory evidence divided by all evidence required for handover; show critical blockers separately.	Before handover; commissioning and operations. A percentage never overrides a blocking criterion.

Measurement rules: Record cutoff, population and source. If the denominator is empty, report "not applicable." Trace reclassification and date changes. Avoid overinterpreting small samples.

Assess process improvement and financial effect separately. A shorter decision cycle does not, by itself, prove savings. Avoided effort and attribution to the intervention require additional evidence.

22 / IMPLEMENTATION AND CONCLUSION

From a focused pilot to a useful PMO

A sensible entry point is a bounded pilot with an active sponsor, clear project accountability and access to the necessary information. The following 90-day structure is a proposed implementation plan. It describes working objectives, not a guaranteed implementation speed for every organization.

Period	Work focus	Output / decision
Days 1-30 Mandate and baseline	Map projects and participants; review scope, schedules, contracts and data quality; identify critical interfaces and scarce roles.	Agreed problem scope, role mandate, baseline measures and a selected pilot process.
Days 31-60 Apply in the project	Use a decision register, interface coordination and reconciled schedule/cost position within existing routines; test readiness criteria.	Reviewable working records, visible open decisions, and feedback from project leadership and operations.
Days 61-90 Evaluate and embed	Compare measures, close data gaps and remove unnecessary effort; assign ongoing ownership and team training.	Decision to continue, adapt or extend. Document usefulness and remaining limitations.

Five questions to answer before starting

1. Which specific execution problem should improve? **2.** Who is accountable for the outcome? **3.** Which decisions may the project leader make? **4.** Which information is authoritative and accessible? **5.** How will the sponsor judge improvement after the pilot?

My position

The United States needs additional and modernized energy infrastructure. It also needs to deliver many interdependent projects under different regional conditions. An effective PMO connects these levels through clear decision routes, comparable maturity and traceable data. Effective project leadership uses that foundation to resolve conflicts and guide the asset to operational handover.

From my experience in medium-voltage projects, industrial development and power-project development, the strongest contribution lies in that connection: understanding technical requirements, structuring work across organizational boundaries, and preparing decisions that convert plans into executable commitments.

The test: critical work is authorized in time, technical and commercial interfaces are closed, and the owner gains a more dependable basis for investment and operating decisions.

REFERENCES / 1 OF 4

Sources and evidence base

Sources were reviewed for the original analysis on November 13, 2026. Links lead to primary sources. Data years, publication dates and company plans are qualified in the relevant sections. This English edition preserves that evidence base.

[1] APPA / EIA | 2026 Public Power Statistical Report
2024 utility counts, p. 18; includes U.S. territories.

[2] Duke Energy | Carolinas Resource Plan: South Carolina
August 17, 2026; Anderson County and generation/storage projects.

[3] NextEra Energy | Financial Policy
Roles of FPL, NextEra Energy Resources and Transmission.

[4] Oncor | Third Quarter 2026 Results
Transmission and distribution utility; connection requests and investment.

[5] North Carolina Electric Cooperatives | About Us
26 local cooperatives; NCEMC supplies 25 members.

[6] Santee Cooper | Investor Relations
Public power provider and wholesale relationship with Central.

[7] Vistra | Our Company
Competitive generation and retail electricity business.

[8] Constellation | Completes Calpine Transaction
January 7, 2026; transaction completion and combined activities.

[9] Burns & McDonnell | Electrical Transmission & Distribution
Service scope: engineering, EPC, project controls and programs.

[10] Quanta Services / SEC | Annual Report 2025, Form 10-K
Filed in 2026; electrical infrastructure and construction services.

[11] FERC | Electric Power Markets
Market structure, ISO/RTO responsibilities and regional jurisdiction.

REFERENCES / 2 OF 4

Sources and evidence base

Sources were reviewed for the original analysis on November 13, 2026. Links lead to primary sources. Data years, publication dates and company plans are qualified in the relevant sections. This English edition preserves that evidence base.

[12] FERC | What FERC Does
Federal responsibilities and the boundary with state regulation.

[13] PUCO Ohio | Data centers and electricity
Cost allocation, financial security and long-term contract requirements.

[14] EIA | U.S. energy facts: data and statistics
Preliminary 2025 energy data; Monthly Energy Review, August 2026. Electricity mix.

[15] EIA | Electricity generation, capacity, and sales in the United States
2025 utility-scale generation: 4,429 TWh; additional small-scale solar generation.

[16] EEI | Industry Capital Expenditures with Functional Detail
2026 capital expenditure plans, as of September 2026; industry association.

[17] Berkeley Lab | United States Data Center Energy Usage Report: 2025 Update
Published June 2026; reference case and scenarios for 2030.

[18] Berkeley Lab | Queued Up: 2026 Edition
Interconnection data through year-end 2025; generation and storage.

[19] MISO | Long Range Transmission Planning
Tranche 2.1: 24 projects, $21.8 billion; targeted in-service dates 2032-2034.

[20] ERCOT | Large Load Interconnection Process: stakeholder engagement plan
December 23, 2025 notice; backlogs, coordination and additional studies.

[21] DOE Office of Electricity | Supply Chain and Market Analysis
Transformer lead times in 2019 and 2023; variation in specifications.

[22] NERC | 2025 Long-Term Reliability Assessment
North American resource adequacy risks; gas-electric dependencies.

REFERENCES / 3 OF 4

Sources and evidence base

Sources were reviewed for the original analysis on November 13, 2026. Links lead to primary sources. Data years, publication dates and company plans are qualified in the relevant sections. This English edition preserves that evidence base.

[23] DOE | Order 413.3C: Program and Project Management for the Acquisition of Capital Assets
August 5, 2026; requirements within the order's DOE scope.

[24] FERC | Explainer: Interconnection Final Rule 2023-A
Explanation of generator interconnection reform; regional implementation matters.

[25] TVA Inspector General | Gallatin Ash Pond Complex Closure and Restoration
Audit 2025-17549, September 23, 2025; cost position as of July 2024.

[26] GAO | Cost Estimating and Assessment Guide, GAO-20-195G
March 12, 2020; methods for transparent, supportable cost estimates.

[27] GAO | Schedule Assessment Guide, GAO-16-89G
December 22, 2015; integrated scheduling and schedule risk.

[28] GE Vernova | Third Quarter 2026 Earnings Press Release
October 28, 2026; global Gas Power backlog and slot reservations.

[29] DOE | 4 Workforce Trends in Nuclear Energy in 2026
USEER survey for 2025; includes construction firms in electric power generation.

[30] Siemens Energy | Investing $1 billion and creating highly skilled jobs in the US
February 3, 2026; expansion including Charlotte and Raleigh.

[31] CAISO | Managing the evolving grid
Solar curtailment, evening ramps, storage and flexibility.

[32] Kinder Morgan | Natural Gas Operations
Natural gas transportation networks and power-generation customers.

[33] Cheniere / SEC | Quarterly Report, September 30, 2026
LNG facilities in Louisiana and Texas; operations and expansion.

REFERENCES / 4 OF 4

Sources and evidence base

Sources were reviewed for the original analysis on November 13, 2026. Links lead to primary sources. Data years, publication dates and company plans are qualified in the relevant sections. This English edition preserves that evidence base.

[34] ExxonMobil | Business divisions
Business structure: Upstream, Product Solutions and Low Carbon Solutions.

[35] Valero | Oil Refining
Refining business and company activities.

[36] DOE | Pathways to Commercial Liftoff: Clean Hydrogen
Chapter 4: offtake, transportation infrastructure and financing.

[37] NRC | Construction permit for Long Mott Generating Station
November 2026; a construction permit is not an operating license.

[38] PJM | Annual Report 2025: Markets
Capacity auction for the 2027/2028 delivery year.

[39] Duke Energy RFP | Carolinas Procurement: SC Battery Program
2026 procurement target: approximately 400 MW of stand-alone, four-hour storage.

[40] ISO New England | Resource Mix
The region's dependence on natural gas and seasonal requirements.

[41] ISO New England | Board Open Meeting: Winter 2026/2027 Outlook
November 10, 2026; expectation of sufficient capacity and energy.

[42] EIA | Short-Term Energy Outlook: Natural Gas
November 2026; U.S. LNG export forecast for 2026/2027.

[43] GE Vernova | Investing in Manufacturing
Includes a planned $160 million manufacturing investment in Greenville County.

[44] GE Vernova | Greenville Service Center, South Carolina
Service, repair and testing capabilities at the site.

How the evidence is used

Government agencies, research institutions and system operators underpin market structure, technical developments and data. Company sources establish the activities and plans those companies publish. Audits address their specific subjects; they are not used as industry-wide statistics.

GAO methods and DOE requirements are treated as reference frameworks. The proposed workflows, roles and measures are my professional interpretation. Their application requires adaptation to the project and organization.

Author: Sven Zeh. **Edition:** November 13, 2026. **Focus:** project development, PMO and technical project leadership in U.S. energy.